




**MIDDLE UPPER GRANDE RONDE RIVER
Fish Habitat & Floodplain Restoration Project**

- █ 2018 Project Boundary
- █ MUGR Phase 2 FY19-20
- █ MUGR Phase 3 FY 21-22
- Spool Cart Campground
- Grande Ronde River Center Line



Spool Cart
Campground

PV Creek

WILLIAMS RIVER


UGR8

Scale


BIOLOGICALLY SIGNIFICANT REACHES

UPPER GRANDE RONDE RESTORATION ATLAS

BSRs updated December 2014 by the Science Technical Advisory Committee.



OREGON




Union
County

LA GRANDE

NAD 1983 UTM Zone 11N
1:350,000




UGR15	UGS17	UGC5	1.1 Habitat Quantity: Anthropogenic Barrier	5%	10%
			4.1 Riparian Condition: Riparian Condition	10%	10%
			4.2 Riparian Condition: LWD Recruitment	10%	10%
			6.2 Channel Structure and Form: Instream Structural Complexity	20%	20%
			7.2 Sediment Condition: Increased Sediment Quantity	15%	10%
			8.1 Water Quality: Temperature	25%	25%
			9.2 Water Quantity: Decreased Water Quantity	15%	15%



HYDRAULIC MODELING AND EXISTING CONDITION ASSESSMENT












LARGE WOOD REFERENCE SITE TIMELAPSE



LARGE WOOD STRUCTURE DESIGN APPROACH/REFERENCES





**MIDDLE UPPER GRANDE RONDE RIVER
Fish Habitat & Floodplain Restoration Project**




- 2019 Phase 1 Project Boundary
- USFS Boundary
- Spool Cart Campground
- Grande Ronde River Center Line
- Helicopter Wood Placement Locations
- Large Wood Placement w/ Site #
- MUGR Temp Access Route
- MUGR Temp Staging Areas




PROJECT MATERIALS SUMMARY


STRUCTURE TYPES AND WOOD SPEC/STRUCTURE	# Structures	Logs w/RW 16" DBH+, 45' L	Tree Tops/Med Wood/Racking (8-14" DBH, 20-30' L
TYPE A - Habitat Structure	22	13	18
TYPE B - Existing Structure Augmentation)	2	10	16
TYPE C - Deflector Structure	10	6	10
TYPE D - APEX Structure	3	4	6
TYPE E - Bleeder Structure	2	7	10
Type F - Floodplain & Misc Channel Wood	82	0	7

Project Materials Summary by Structure Type		
TYPE A - Habitat Structure	286	396
TYPE B - Existing Structure Augmentation)	20	32
TYPE C - Deflector Structure	60	100
TYPE D - APEX Structure	12	18
TYPE E - Bleeder Structure	14	20
Type F - Floodplain & Misc Channel Wood	0	574
MATERIALS SUMMARY	392	1140


WOOD MATERIAL SPECIFICATIONS	
Wood Material	Material Size
	16"+ DBH, 45' L (Top layer of structure)
	16"+ DBH, 45' L (Base Layer of Structure)
	8-15" DBH < 30'+ L (Racking Logs)







1 PLAN VIEW
HORIZ 1" = 30'




2 SECTION VIEW
HORIZ 1" = 20'


TYPE A LARGE WOOD STRUCTURE BIOLOGICAL OBJECTIVES - DESIGN INTENT

- PURPOSE OF TYPE A LARGE WOOD STRUCTURE IS TO CREATE A STRUCTURE THAT INCREASES WATER SURFACE ELEVATION AND DEPTH, DECREASES WATER VELOCITY, PROMOTES SEDIMENT DEPOSITION AND STORAGE, PROVIDES HABITAT COVER AND COMPLEXITY, AND PROMOTES FLOODPLAIN CONNECTIVITY AND INCREASED GROUNDWATER AND HYPOHEIC FUNCTIONS TO IMPROVE WATER TEMPERATURE DIVERSITY AND COLD WATER REFUGE.
- PROMOTES DEVELOPMENT AND MAINTENANCE OF LARGE POOL HABITAT, PROVIDES OVERHEAD COVER, VELOCITY REFUGE, AND ORGANIC NUTRIENTS THAT SUPPORT FOOD WEB PROCESSES.


STEP 1 - Install small logs/racking material on streambed as shown to form base of wood structure



STEP 2 - Place large logs on top of small logs as shown



STEP 3 - Place additional racking logs followed by large logs as shown. Key member log trenching illustrated in dashed line (applicable for ground-based placement structures).



3 ASSEMBLY DETAIL & INSTALLATION SEQUENCE
HORIZ 1" = 50'

PROJECT ELEMENT NOTES

- WOOD MATERIAL SHALL COME FROM FIR, SPRUCE, LODGEPOLE PINE, OR PINE TREES.
- LOCATION OF WOOD STRUCTURE SHALL BE STAKED AT EACH LOCATION BY CO.
- WOOD STRUCTURE SHALL BE CONSTRUCTED EITHER BY TRACK MOUNTED EXCAVATOR, HELICOPTER, AND/OR A COMBINATION OF THE TWO BASED ON GROUND-BASED ACCESS FEASIBILITY.
- STRUCTURE WILL BE CONSTRUCTED IN LAYERS FOLLOWING THE ASSEMBLY DETAIL ILLUSTRATED ABOVE.
- STRUCTURE WILL BE INITIATED BY PLACING BASE WOOD MATERIAL, FOLLOWED BY LARGE KEY MEMBER LOGS AND INTERWOVEN WITH ADDITIONAL RACKING MEMBERS.
- TOP KEY MEMBER LOGS WILL BE PLACED LAST, OVER-TOPPING BASE MEMBERS TO PROVIDE BALLAST AND ANCHORING OF UNDERLYING WOOD MATERIAL AS DIRECTED BY CO.
- TYPE A STRUCTURES ACCESSIBLE BY GROUND-BASED EQUIPMENT (DELINEATED IN PLANVIEW SHEETS) WILL INCLUDE TRENCHING AND BURYING 3-4 KEY MEMBER LOGS AND BACK-FILLED WITH COMPACTED BACKFILL TO PROVIDE STRUCTURAL STABILITY AND BALLAST. TRENCHES WILL TYPICALLY BE 35-40 FEET IN LENGTH, 3 FEET WIDE AND 4 FEET DEEP.
- BOULDERS WILL BE PLACED IN WOOD STRUCTURES ACCESSIBLE BY GROUND-BASED EQUIPMENT TO WEDGE KEY MEMBERS AND PROVIDE ADDITIONAL BALLAST FOR STRUCTURAL STABILITY.

MATERIAL SCHEDULE

ITEM	QUANTITY	DIA. (IN)	LENGTH (FT)	ROOTWAD (Y/N)
LARGE LOG W/RW	13	16" Plus	~ 45' plus	YES - 5" DIA. MIN.
RACKING LOGS/TOPS	18	8-16"	~ 20-30'	NO

SUMMARY OF QUANTITIES

Large Wood Structures	Quantity	Unit
TYPE I (Channel Spanning wood structure)		
# Structures	21	each
Key member w/RW, (18" dbh+, 45'+ L	231	each
Racking Logs/tops, 8-14" dbh, 20-30' L	336	each
TYPE II (Similar to Type I, constructed on existing structure)		
# Structures	4	each
Key member w/RW, (18" dbh+, 45'+ L	24	each
Racking Logs/tops, 8-14" dbh, 20-30' L	64	each
TYPE III (Deflector)		
# Structures	10	each
Key member w/RW, (18" dbh+, 45'+ L	50	each
Racking Logs/tops, 8-14" dbh, 20-30' L	100	each
TYPE IV (Apex)		
# Structures	3	each
Key member w/RW, (18" dbh+, 45'+ L	8	each
Racking Logs/tops, 8-14" dbh, 20-30' L	12	each
TYPE V (Bleeder)		
# Structures	3	each
Key member w/RW, (18" dbh+, 45'+ L	21	each
Racking Logs/tops, 8-14" dbh, 20-30' L	12	each
TYPE VI (Whole Trees)		
# Structures	29	each
Key member w/RW, (18" dbh+, 45'+ L	0	each
Racking Logs/tops, 8-14" dbh, 20-30' L	0	each
Floodplain/Large Wood Augmentation		
Small-Medium Whole Trees/Logs 6-14" DBH, 20-30" L	200	each
SUMMARY		
Total large Wood Structures	70	each
Total Key Member Pieces of Wood, 18"+ DBH, 45' L	363	each
Total Racking Material (Logs/Treetops, 8-14" DBH, 20-30' L	533	each
Total Floodplain Augmentation Logs, 8-14" DBH, 20-30' L	200	each

SUMMARY

- 40 Engineered Wood Treatment Sites
- 31 Whole Tree Placements
- 200 Pieces Wood Augmentation

CONSTRUCTION METHOD

- 25 ELJ Sites (63%) Helicopter Placement
- 15 ELJ Sites (37%) Ground Based Placement
- 31 Whole Tree Placements
- 200 Pieces Wood Augmentation

STRUCTURE TYPES AND WOOD SPEC/STRUCTURE	COUNT	Per Each	
		Log w/RW 18" DBH+, 45' RACKING	(8-14" DBH, 20-30' LENGTH
TYPE I (Channel Spanning Structure)	21	11	16
TYPE II (Channel Spanning Structure (on Existing Structure)	4	6	16
TYPE III (Deflector Structure)	10	5	10
TYPE IV (APEX Structure)	2	4	6
TYPE V (Bleeder Structure)	3	7	7
Type VI (Large Whole Trees)	29	1	0
Floodplain/Augmentation Wood - Small-Med whole tree/logs no RW 6-14" DBH, 20-30' L	200	0	200
TYPE I		231	336
TYPE II		24	64
TYPE III		50	100
TYPE IV		8	12
TYPE V		21	21
TYPE VI		29	0
FP/Augmentation Wood - Sm-Med WT/logs no RW 6-14" DBH, 20-30' L		0	200
MATERIALS SUMMARY		363	733